

TOWN OF WEST SENECA



ENGINEERING DEPARTMENT

TOWN SUPERVISOR
SHEILA M. MEEGAN
TOWN COUNCIL
EUGENE P. HART
WILLIAM P. HANLEY JR.

April 21, 2014

Honorable Town Board
Town of West Seneca

**Re: Award of Contract
Commerce Parkway Road Reconstruction**

Honorable Board Members,


On April 16, 2014, we received four (4) separate bids for the reconstruction of Commerce Parkway and Ransier Drive. The project includes full depth road reconstruction and replacement of the drainage structures. Bids ranged from a low of \$1,285,623.70 to a high of 1,737,029.40. The Engineer's estimate was \$1,451,173.30

The low bidder was Union Concrete Corp. from West Seneca, NY with a bid amount of 1,285,623.70. The Town recently worked with Union Concrete on the emergency Lexington Green flood control project and the experience was very favorable. They are comfortable with their bid prices and have indicated that they have the equipment and personnel to complete the work.

We recommend that the Town Board pass a resolution "**Accepting the Base Bid received from Union Concrete, Corp. for the Reconstruction of Commerce Parkway, and awarding the Contract to them**".

Please note this contract will be funded as a capital improvement project via a previously approved Bond Resolution. Once the project has been awarded, we will provide the Contractor with the Notice of Award and copies of the agreement for their execution. When returned, the executed agreements will be sent to the Board for the signature of the Supervisor.

Very truly yours,


Richard B. Henry III, P.E. *DHS*
Town Engineer

cc: Files: TB.
Project

TABULATION OF BIDS

OWNER: TOWN OF WEST SENECA
 PROJECT: Commerce Parkway & Ransier Drive Reconstruction
 JOB NO: CPL - 13111.00
 BID DATE: 4/16/14 2pm

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS	Union Concrete & Construction Corp.	
				P.O. Box 410	West Seneca, NY 14224
201.06000000	Clearing & Grubbing	1	LS	\$ 5,000.00	\$ 5,000.00
203.02000000	Unclassified Excavation & Disposal	7829	CY	\$ 7.25	\$ 56,750.25
203.03000000	Embankment in Place	329	CY	\$ 18.00	\$ 5,922.00
203.70000000	Select Granular Fill	183	CY	\$ 45.00	\$ 8,235.00
203.24010017	Shoulder Backup Material	15	TON	\$ 30.00	\$ 450.00
204.01000000	Controlled Low Strength Material	4	CY	\$ 85.00	\$ 340.00
206.02010000	Trench & Culvert Excavation	3000	CY	\$ 35.00	\$ 105,000.00
206.03000000	Conduit Excavation & Backfill Including Surface Restoration	25	LF	\$ 21.00	\$ 525.00
206.04000000	Trench & Culvert Excavation O.G.	0	CY	\$	\$
207.21000000	Geotextile Separation	9443	SY	\$ 0.90	\$ 8,498.70
207.24000000	Geotextile Stabilization	9443	SY	\$ 2.00	\$ 18,886.00
209.13000000	Silt Fence - Temporary	1542	LF	\$ 1.60	\$ 2,467.20
209.17020000	Drainage Structure Inlet Protection, Gravel Bag - Temporary	18	CY	\$ 175.00	\$ 3,150.00
304.12000000	Subbase Course, Type 2	151	CY	\$ 50.00	\$ 7,550.00
304.15000000	Subbase Course, Optional Type	4710	CY	\$ 25.00	\$ 117,750.00
402.12830200	12.5 F3 Top Course HMA, 80 Series Compaction	891	TON	\$ 74.00	\$ 65,934.00
402.12831200	Plant Production Quality Adjustment to 402.128302	45	QU	\$ 75.00	\$ 3,375.00
402.25890200	25 F9 Binder Course HMA, 80 Series Compaction	1436	TON	\$ 67.00	\$ 96,212.00
402.25891200	Plant Production Quality Adjustment to 402.378902	72	QU	\$ 75.00	\$ 5,400.00
402.37890200	37.5 F9 Base Course Hma, 80 Series Compaction	3329	TON	\$ 64.00	\$ 213,056.00
402.37891200	Plant Production Quality Adjustment 402.378902	166	QU	\$ 75.00	\$ 12,450.00
407.01020000	Diluted Tack Coat	1130	GAL	\$ 5.00	\$ 5,650.00
552.17000000	Shields & Shoring	2000	SF	\$ 1.00	\$ 2,000.00
603.60010000	Reinforced Concrete Pipe Class III, 12" dia.	10	LF	\$ 75.00	\$ 750.00
603.98120000	Smooth Interior Corrugated Polyethylene Culvert & Storm Drain - 12" dia.	1095	LF	\$ 7.00	\$ 7,665.00
603.98160000	Smooth Interior Corrugated Polyethylene Culvert and Storm Drain - 18" dia.	345	LF	\$ 14.00	\$ 4,830.00
603.98240000	Smooth Interior Corrugated Polyethylene Culvert and Storm Drain - 24" dia.	723	LF	\$ 19.00	\$ 13,737.00
603.98360000	Smooth Interior Corrugated Polyethylene Culvert & Storm Drain - 36" dia.	35	LF	\$ 55.00	\$ 1,925.00
603.98600000	Smooth Interior Corrugated Polyethylene Culvert & Storm Drain - 60" dia.	902	LF	\$ 95.00	\$ 85,690.00
604.07040100	Altering Drainage Structures, Leaching Basins & Manholes	15	EA	\$ 1.00	\$ 15.00
604.30191100	Rectangular Drainage Structure	34	LF	\$ 220.00	\$ 7,480.00
604.30201600	Rectangular Drainage Structure Type T for #16 Welded Frame	5	LF	\$ 275.00	\$ 1,375.00
604.40480000	Round Precast Manhole Type 48	30	LF	\$ 205.00	\$ 6,150.00
604.40600000	Round Precast Manhole Type 60	5	LF	\$ 400.00	\$ 2,000.00
604.40120000	Round Precast Manhole Type 120	5	LF	\$ 1,800.00	\$ 9,000.00
604.50040100	Special Drainage Structure	10	LF	\$ 3,000.00	\$ 30,000.00
605.10010000	Underdrain Filter Type 2	500	CY	\$ 50.00	\$ 25,000.00
605.17020000	Optional Underdrain Pipe, 6" diameter	6,044	LF	\$ 1.90	\$ 11,483.60
608.01010000	Concrete Sidewalks & Driveways	5	CY	\$ 500.00	\$ 2,500.00
608.02010200	Hot Mix Asphalt (HMA) Sidewalks, Driveways, Bicycle Paths & Vegetation Control Strips	93	TON	\$ 150.00	\$ 13,950.00
608.02011200	Plant Production Quality Adjustment to 608.020112	5	QU	\$ 75.00	\$ 375.00
608.21000000	Embedded Detectable Warning Units	3	SY	\$ 350.00	\$ 1,050.00
609.04010000	Cast-in-Place Concrete Curb Type VF150	716	LF	\$ 21.00	\$ 15,036.00
610.14020000	Topsoil - Roadside	222	CY	\$ 45.00	\$ 9,990.00
610.16010000	Turf Establishment - Roadside	2,689	CY	\$ 1.00	\$ 2,689.00
615.02050124	Remove, Store & Reset Boulder, Type 01	10	EA	\$ 25.00	\$ 250.00
619.01000000	Basic Work Zone Traffic Control	1	LS	\$ 25,000.00	\$ 25,000.00
619.27000000	Mailboxes	13	EA	\$ 120.00	\$ 1,560.00
624.01090000	Conventionally Formed or Machine Formed Concrete Gutters - Type BB	15,048	SF	\$ 5.50	\$ 82,764.00
627.50140008	Cutting Pavement	2,389	LF	\$ 1.90	\$ 4,539.10
637.11000000	Engineer's Field Office - Type 1	4	MO	\$ 1,100.00	\$ 4,400.00
645.51010000	Ground-Mounted Sign Panels Without Z-Bars	9	SF	\$ 70.00	\$ 630.00
645.52010000	Ground-Mounted Sign Panels Without Z-Bars - High Visibility Sheeting	35	SF	\$ 37.00	\$ 1,295.00
645.81000000	Type A Sign Posts	12	EA	\$ 210.00	\$ 2,520.00
647.61000000	Rem & Dispose Ground Mounted Type A Sign Support(S), Fdns & any Attached Signs - Size 1 (under 30 SF)	14	EA	\$ 11.00	\$ 154.00
652.01000000	Furnish & Applying Calcium Chloride	3	TON	\$ 500.00	\$ 1,500.00
655.10160000	Welded Frame & Rectangular Grate 16	1	EA	\$ 1,100.00	\$ 1,100.00
655.11030000	Welded Frame & Recticuline Grate 3	0	EA	\$	\$
655.11110000	Welded Frame & Recticuline Grate 11	12	EA	\$ 850.00	\$ 10,200.00
663.33000000	Adjusting Existing Valve Box Elevation	1	EA	\$ 500.00	\$ 500.00
680.51010100	Pulbox-Circular 15" dia. Rein. Concrete	1	EA	\$ 790.00	\$ 790.00
680.52010600	Conduit, Metal Steel, Zinc Coated, 2"	20	LF	\$ 10.50	\$ 210.00
680.54000000	Inductance Loop Installation	208	LF	\$ 10.50	\$ 2,184.00
680.71000000	Shielded Lead-in Cable	25	LF	\$ 1.25	\$ 31.25
680.72000000	Inductance Loop Wire	624	LF	\$ 1.15	\$ 717.60
685.11000000	White epoxy Reflectorized Pavement Stripes - 20 Mils	546	LF	\$ 3.50	\$ 1,911.00
685.12000000	Yellow Epoxy Reflectorized Pavement Stripes - 20 Mils	5,540	EA	\$ 0.90	\$ 4,986.00
685.13000000	White epoxy Reflectorized Pavement Stripes - 20 Mils	8	EA	\$ 60.00	\$ 480.00
685.14000000	White epoxy Reflectorized Pavement Symbols - 20 Mils	8	EA	\$ 225.00	\$ 1,800.00
698.04000000	Asphalt Price Adjustment	1	DC	\$ 20,000.00	\$ 20,000.00
698.05000000	Fuel Price Adjustment	1	DC	\$ 25,000.00	\$ 25,000.00
699.04000100	Mobilization	1	LS	\$ 49,000.00	\$ 49,000.00
603.17222120	End Sections	2	EA	\$ 2,400.00	\$ 4,800.00
	Allowance	1	LS	\$ 40,000.00	\$ 40,000.00
TOTAL				\$	\$ 1,285,623.70